

Job Information Technical Data Sheet

Job Name Unit Tag SFL Parts WSHP Partners Program

2.0 Ton RH



Unit Overview											
Model Number	Voltage V/Hz/Phase	Airflow CFM	Fluid Flow gpm	Cooling Capacity Btu/hr	Cooling Efficiency EER @ AHRI	Heating Capacity Btu/hr	Heating Efficiency COP @ AHRI				
WGCV024	208-230/60/1	836	6.00	22006	13.5	26549	4.5				

Unit						
Model Number:	WGCV024					
Unit Type:	it Type: Compact Vertical Single Stage					
Approval:	ETL, CETL, AHRI					
Configuration	Refrigerant Type	Refrigerant Weight	Loop Temperature Range			
Vertical	R-410Δ	32 0 07	Water Loon (Standard Range)			

Unit Perfo	rmance										
Air & Water Flow											
Airflow Total		Total Ext	l External Static Pressure		Fluid Flow		Fluid Type		Altitude		
836 сғм			0.30 inH₂O	0 inH ₂ O 6.00 gpm / 3.00 g		pm/ton	Water		0 ft		
	Cooling Performance										
Fluid Tem	Fluid Temperature		Air Temp	Air Temperature		Capacity		Heat of	EER (<u> </u>	Fluid
Entering	Leaving	Ent	tering	Lea	Leaving Total			Rejection	AHR	I	Pressure
°F	°F	F Dry Bulb °F	Wet Bulb °F	Dry Bulb °F	Wet Bulb °F	Btu/h	nr Btu/hr	Btu/hr			Drop ft H₂O
90.0	99.6	75.0	63.0	56.4	53.8	2200	16826	28829	13.5	5	12.13
				He	ating Performa	nce					
Flui	d Temperature		Air Temperature		(Capacity Heat of		СОР	@ AHRI F		Fluid Pressure
Entering		ving	Entering	Leavin	g	Total	Absorption	1			Drop
°F		°F	Dry Bulb °F °F		lb	Btu/hr	Btu/hr				ft H₂O
70.0	63	3.0	70.0	99.2		26549	21131		4.5		12.56

^{*}System WPD is calculated without the autoflow valve as the CV of an autoflow valve varies dependent on the system WPD. As long as the WPD is >3 psid, the autoflow valve will provide the selected GPM flowrate.

Electrical									
Unit Voltage	Minimum Voltage	Total Unit Full Load Current	Total Unit MCA						
208-230/60/1	197.0 v	16.40 A	19.77 A						
Compressor RLA	Compressor LRA	Motor FLA	Maximum Recommended Fuse Size / HACR Breaker Size						
13.5 A	58.3 A	2.90 A	30 A						

Physical									
Unit									
Depth	Depth Height		We	eight	Connection				
			Shipping	Operating	Water	Condensate			
21.50 in	39.00 in	21.50 in	197 lb	169 lb	0.75 in	0.75 in			
Fan									
	Motor Type	•		Motor Horsepower					
ECM Constant Torque				0.33 hp					

Discharge Air Location:



Unit Options Controls Unit Control: Microtech III Control Transformer: Standard 50 VA Transformer Thermostat / Sensor Control: Thermostat Control Unit Airflow Configuration Return Air Location: Right Hand

Factory Mounted Options

Coaxial Heat Exchanger Options

Heat Exchanger: Copper Inner Tube / Steel Outer Tube

Top

Construction Options Drain Pan Material Primary: Stainless Steel **Filters** Filter Rack Type: 1-inch Rail Filter Type: Standard 1 inch (Quantity) Filter Dimensions: (1) 20 in x 20 in x 1 in Insulation Compressor Compartment: 1/2 inch Fiberglass, Skin-faced Air Compartment: 1/2 inch Fiberglass, Skin-faced

Warranty


Unit Warranty: 1st Year Labor Allowance


AHRI Certification





All equipment is rated and certified in accordance with AHRI / ISO 13256-1 and tested, investigated, and determined to comply with the requirements of the standards for Heating and Cooling Equipment UL-1995 for the United States and CAN/CSA-C22.2 NO.236 for Canada.

3/4 VIEW - RIGHT HAND RETURN UNIT









NOTES						
[A] - High Volt Pwr Entry 1.1 DIA	[B] - Low Volt Pwr Entry 0.8 DIA	[C] - Condensate Drain 3/4" FPT				
[D] - Supply Water 3/4" FPT	[E] - Return Water 3/4" FPT	[F] - Unit Front Service Clearance 24				

Product Drawing	Unit Tag: 2.0 Ton RH			DAIKIN			
Product:	Project Name:	: SFL Parts WSHI	Partners Progr	am 13600 Industrial Park Blvd. Minneapolis, MN 55441			
Model: WGCV024	Sales Office: Daikin Applied South Florida			www.DaikinApplied.com Software Version: 07.20			
Sales Engineer:	Dec. 10, 2018			Scale: NTS	Tolerance: +/-0.25"	Dwg Units: (in)	
Sales Engineer.	Dec. 10, 2010	ver/nev.	SHEET TOT I	Scarc. 1415	Toterance: 1/-0.25	DWg Offics. (III)	

No change to this drawing may be made unless approved in writing by Daikin Applied. Purchaser must determine that the equipment is fit and sufficient for the job specifications.